# BRUHATH BENGALURU MAHANAGARA PALIKE

## Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-01/2020-21 Dt:02-5-2020

## APPROVED TENDER SCHEDULE –'B'

Item 57

Name of Work :-Emergency works in ward no 04

| Sl | Description | Unit | Approved Qty | Rate quoted by the contractor approved rates Sri B P MAHESH ( M/S SRI SAI MANJUNATHA ENTERPRISES ) | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | KSRRB 3001 Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 0.5 m excavated surface levelled and sides neatly dressed the disposed earth to be levelled neatly after breaking of clods complete as per specifications MORTH Chapter 3 P No 143 I No 19 1 | Cum | 300.00 | 250.24 | Two Hundred Fifty Paise TwentyFour Only |
| 2 | KSRB 2 2 1Earthwork excavation by manual means for foundation of buildings culverts water supply and sanitary lines and electrical conduits etc either in pits or in trenches 1.5m and above in width in ordinary soil not exceeding 1 5 m in depth including dressing the bottom and sides of pits and trenches stacking the excavated soil clear from edges of excavation with lead up to 50 m including breaking of clods complete as per specifications No KBS 2 1 a Item No 2 3 5 Page no 6 | Cum | 180.00 | 376.38 | Three Hundred SeventySix Paise ThirtyEight Only |
| 3 | Providing precast slab of 100mm tick including cost of all materials labour curing transportation loading unloading etc complete as per the direction | Sqm | 64.80 | 2337.00 | Two Thousand Three Hundred ThirtySeven Only |
| 4 | Providing precast slab of 250mm tick including cost of all materials labour curing transportation loading unloading etc complete as per the direction | Sqm | 18.00 | 5418.00 | Five Thousand Four Hundred Eighteen Only |
| 5 | Engaging on Hire Basis JCB including Driver operator with fuel etc complete SR 2018-19 Page No XLVIII code 1031 of engineer in charge | Day | 15.00 | 5695.00 | Five Thousand Six Hundred NinetyFive Only |

| | | | | | |
|---|---|---|---|---|---|
| 6 | Engaging on Hire basis of Tractor 40 HP for Conveying of excavated and removal of Stuff from work spot SR 2018-19 Page No XLVIII code 1024 | Day | 180.00 | 1288.00 | One Thousand Two Hundred EightyEight Only |
| 7 | Providing causal Labour Unskilled Mazdoor Heavy Page no LVI SR 2018 19 sl No 5 | Nos | 1440.00 | 436.20 | Four Hundred ThirtySix Paise Twenty Only |

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.